


**INSTALLATION OF DUCT TYPE AC SYSTEM INCLUDING ALL ACCESSORIES  
FAISALABAD INSTITUTE OF CARDIOLOGY, FAISALABAD**

Sr. No.	Item Name	Qty
1.	Split Ducted Type A.C Unit, Capacity 8 TR, Complete Service of Condensing unit, Indoor Fan Coil Unit	02 Nos
2.	8TR A.C old Compressor Dismantling, New Compressor Fitting, Other Maintenance, (Filter, Safety Devices, any Leakage with Pressure Testing etc) etc	02 Nos
3.	8 TR A.C Unit Gas Service/Gas Stop Valve 1" & 5/8, Line size providing & Fitting	02 Set
4.	8 TR A.C Unit Installation Indoor Fan Coil Unit, Outdoor Condensing Unit	02 Nos
5.	8 TR A.C Unit System Vacuum, Gas R-22 Charging, Testing etc	02 Nos
6.	4 TR Split Ducted Type A.C Unit, Capacity Complete Service of Condensing unit, Indoor Fan Coil Unit	08 Nos
7.	4 TR A.C old Compressor Dismantling, New Compressor Fitting, Other Maintenance, (Filter, Safety Devices, any Leakage with Pressure Testing etc) etc	08 Nos
8.	4 TR A.C Unit Gas Service/Gas Stop Valve 7/8" & 1/2, Line size providing & Fitting	08 set
9.	8 TR A.C Unit Installation Indoor Fan Coil Unit, Outdoor Condensing Unit	08 Nos
10.	8 TR A.C Unit System Vacuum, Gas R-22 Charging, Testing etc	08 Nos
11.	G.I sheet Metal work for Indoor Unit Duct Plenum for Air Distribute with Installation	10 Nos
12.	Flexible Round duct Dia 6" Imported, Factory Fabricated.	250 Rft
13.	Supply air Diffuser with VCD, providing & fitting	40 Nos
14.	Both A.C Capacity, Refrigerant Copper piping (Liquid & Gas) Line, with insulation, Taping, clamping control wire etc	01 Rft
15.	Condensate drain pipe line (U-PVC material ) 1" dia fabrication, fitting, leveling etc	01 Rft
16.	Flexible round duct dia 6" with insulated imported, factory fabricated, for supply air	560 Rft
17.	Flexible round duct dia 8" with insulated imported, factory fabricated, for supply air	190 Rft
18.	supply Air round diffuser with VCD, providing & fitting	46 Nos
19.	Return Air round diffuser with VCD, providing & fitting	12 Nos
20.	Dummy Grill for retrun air 12" x18"	6 Nos

CG ✓

21.	Return Ari Grill with filter 12x18	6 Nos
22.	Wire mesh filter in Plenum Box for Cath Lab Unit	6 Nos
23.	Plenum Box Make with GI Sheets/Fiber Sheet, Hanging support etc supply & return side	12 Nos
24.	Copper pipe , insulation , taping electric control wiring etc	450 Rft
25.	Condensate Drain Pipe Line (U-PVC Material) 1" Dia Fabrication, fitting , Leveling etc	250 Rft
26.	5-8 TR A.C Unit Gas Service/Gas Stop Valve 1" & 5/8, Line size providing & Fitting	6 Set
27.	Bracket Stand for outer unit, floor mounted & wall hanging type complete rawal bolts, Nuts, Paint etc	6 Nos
28.	Ducted type unit, providing & installation of copland scroll type compressor	2 Nos
29.	Ducted type unit complete master servicing cleaning etc	6 Nos
30.	Ducted type unit installation Indoor & outdoor unit, supporting Hanger etc	6 Nos
31.	Ducted Type Unit Gas Leakage Test, Gas R-410a Charging etc.	6 Nos

  
**Medical Superintendent**  
 Faisalabad Institute of Cardiology,  
 Faisalabad.